# Public Document Pack Winchester City Council

**Meeting** Business and Housing Policy Committee

**Date and Time** Wednesday, 12th July, 2023 at 6.30 pm.

Venue Walton Suite, Winchester Guildhall

#### SUPPLEMENTARY AGENDA

Agenda Item.

7. Retrofit housing programme (Pages 3 - 16)

City Offices Colebrook Street Winchester SO23 9LJ Laura Taylor Chief Executive


All of the Council's publicly available agendas, reports and minutes are available to view and download from the Council's <u>Website</u> and are also open to inspection at the offices of the council. As part of our drive to minimise our use of paper we do not provide paper copies of the full agenda pack at meetings. We do however, provide a number of copies of the agenda front sheet at the meeting which contains the QR Code opposite. Scanning this code enables members of the public to easily access all of the meeting papers on their own electronic device. Please hold your device's camera or QR code App over the QR Code so that it's clearly visible within your screen and you will be redirected to the agenda pack.



7 July 2023

Agenda Contact: Matthew Watson, Senior Democratic Services Officer

Tel: 01962 848 317 Email: mwatson@winchester.gov.uk






Page 3


**Business & Housing Policy Committee** 

12th July 2023




### **Council Homes - EPC SAP Bandings (66% Band C or above)**





### **Council Homes – SAP Rating (average SAP 70.55)**





# Average running costs: GAS (System boiler)

					-				-	
		Energy			Costs				Carbon	
Energy efficiency measures	Indicative specification / notes	EPC EPC	Total annual energy	Annual energy saving	Total fuel	Saving on fuel bill			Carbon emissions	
			kWh/yr/yr	kWh/yr/yr	£/yr	£/yr	(£)	(years)		(tonnes/ yr)
Baseline	Assumes no cavity wall insulation, no loft insulation and windows ~20 years old	57D	21992	-	£2,698.27	n/a	0	n/a	4.17	n/a
Wall only	Cavity wall insulation	63D	18628	3364	£2,340.67	£357.59	2000	5.59	3.53	0.64
Loft only	Loft insulation to 0.16 U-value	63D	18317	3675	£2,307.61	£390.65	1500	3.84	3.47	0.7
Windows & doors only	Windows and doors to 1.40 U-value	59D	21008	984	£2,593.67	£104.60	4300	41.11	3.99	0.18
All fabric - walls, loft, windows and doors	As above	71C	13457	8535	£1,791.00	£907.27	7800	8.60	2.55	1.62
All fabris + Mixergy cylinder	All fabric as above Mixergy cylinder – 210l	72C	13113	8879	£1,754.43	£943.84	9200	9.75	2.47	1.70
All fabric + Mixergy cylinder + PV with solar diverter	Mixergy cylinder as above + 3.63kWp solar PV -Note that the majority of the benefit comes from the solar PV.	81B	10175.7	11816.3	£1,310.95	£1,387.32	14700	10.60	1.82	2.35
Uninsulated + Mixergy cylinder	No fabric upgrades Mixergy cylinder – 210l	59D	21636	356	£2,660.42	£37.84	1400	37.00	4.09	0.08
Uninsulated + Mixergy cylinder + PV with solar diverter	Mixergy cylinder as above + 3.63kWp Note that the majority of the benefit comes from the solar PV.	67D	18690.7	3301.3	£2,216.09	£482.17	6900	14.31	3.45	0.72



All values are approx.

# Average running costs: GAS (combi boiler)

		Energy			Costs				Carbon		
Energy efficiency measures	Indicative specification / notes	EPC	EPC	Total annual energy	Annual energy saving	Total fuel	Saving on fuel bill	Capital cost	Simple payback	Carbon emissions	Annual carbon saving
				kWh/yr/yr	kWh/yr/yr	£/yr	£/yr	(£)	(years)	(tonnes/ yr)	(tonnes/ yr)
Baseline	Assumes no cavity wall insulation, no loft insulation and windows ~20 years old	57	D	21993	-	£2,698.37	n/a	0	n/a	4.17	n/a
Wall only	Cavity wall insulation	63	D	18641	3352	£2,342.05	£356.32	2000	5.61	3.53	0.64
Loft only	Loft insulation to 0.16 U-value	63	D	18330	3663	£2,309.00	£389.38	1500	3.85	3.47	0.7
Windows & doors only	Windows and doors to 1.40 U-value	59	D	21018	975	£2,594.73	£103.64	4300	41.49	3.99	0.18
All fabric - walls, loft, windows and doors	As above	71	С	13493	8500	£1,794.82	£903.55	7800	8.63	2.55	1.62
All fabric + Sunamp	There is no benefit from installing a Sunamp on its own, without the PV			0		£0.00					
All fabric + Sunamp + PV with solar diverter	3.63kWp PV + Sunamp Thermino ePV	87	В	11053	10940	£1,394.35	£1,304.02	15800	12.12	2.15	2.19
Uninsulated + Sunamp	There is no benefit from installing a Sunamp on its own, without the PV			0		£0.00					
Uninsulated + Sunamp + PV with solar diverter	3.63kWp PV + Sunamp Thermino ePV	73	С	19585	2408	£2,301.31	£397.07	8000	20.15	3.77	0.40

All values are approx.



# Average running costs: Electric (quantum)

	9							<b>\</b> 1		,		
				Energy	Energy		Costs				Carbon	
Energy efficiency measures	Indicative specification / notes	EPC	EPC	Total annual energy	Annual energy saving	Total annual fuel bill	Saving on fuel bill	Capital cost	Simple payback	Carbon emissions	Annual carbon saving	
				kWh/yr/yr	kWh/yr/yr	£/yr	£/yr	(£)	(years)	(tonnes/ yr)	(tonnes/ yr)	
Baseline	Assumes no cavity wall insulation, no loft insulation and windows ~20 years old	2	0G	18928	-	£4,703.72	n/a	0	n/a	2.30	n/a	
Wall only	Cavity wall insulation	2	9F	15925	3003	£3,980.35	£723.38	2000	2.76	1.92	0.38	
Loft only	Loft insulation to 0.16 U-value	3	0F	15650	3278	£3,914.02	£789.70	1500	1.90	1.89	0.41	
Windows & doors only	Windows and doors to 1.40 U-value	2	3F	18047	881	£4,491.50	£212.22	4300	20.26	2.19	0.11	
All fabric - walls, loft, windows and doors	As above	4	7E	11394	7534	£2,888.84	£1,814.88	7800	4.30	1.36	0.94	
All fabrite Mixergy cylinder	All fabric as above Mixergy cylinder – 210l	4	8E	11147	7781	£2,833.11	£1,870.61	9200	4.92	1.33	0.97	
All fabric + Mixergy cylinder + PV with solar diverter	Mixergy cylinder as above + 3.63kWp solar Note that the majority of the benefit comes from the solar PV.	6	3 D	8645	10283	£2,179.67	£2,524.05	14700	5.82	0.96	1.34	
Uninsulated + Mixergy cylinder	No fabric upgrades Mixergy cylinder – 210l	2	1F	18667	261	£4,644.68	£59.04	1400	23.71	2.27	0.03	
Uninsulated + Mixergy cylinder + PV with solar diverter	Mixergy cylinder as above + 3.63kWp solar PV.	3	1F	16162	2766	£3,974.06	£729.67	6900	9.46	1.89	0.41	
All fabric + Sunamp	There is no benefit from installing a Sunamp on its own, without the PV											
All fabric + Sunamp + PV with solar diverter	3.63kWp PV + Sunamp Thermino ePV	6	6D	8614	10314	£2,224.38	£2,479.34	15800	6.37	0.95	1.35	
Uninsulated + Sunamp	There is no benefit from installing a Sunamp on its own, without the PV											
Uninsulated + Sunamp + PV with solar diverter	3.63kWp PV + Sunamp Thermino ePV	3	3F	16127	2801	£4,019.88	£683.84	8000	11.70	1.89	0.41	

All values are approx.



Planned "Insulate" Works `23/`24	Props	Measures	Est.Cost
Part 1- Measures & Costs			(`000)
Voids - internal wall insulation (IWI)	4	20	150
SHDF - Year 1 - 40% - Swedish cottages	8	48	800
SHDF - Year 1 - 40% - loft insulation top-ups/ventilation	140	140	280
RR - Energy assessments	800	0	160
RR - Insulation top-up and/or ventilation	150	450	000
	150	150	300
RR - Cavity wall suck-outs/refills	150 60	150	300
RR - Single glazed window replacements	30	60	240 18
ນ RR - Single-glazed door replacements ົດ	30	30	10
Φ Ovoids - houses, bungalows and top floor flats (loft insulation)	160	160	320
Voids - houses & bungalows (cavity insulation)	140	140	280
voide modeou a bangaione (bavity modiation)	140	140	200
		898	2848
No. of properties receiving energy improvements	522		20.0
The composition receiving energy improvements	022		
SHDF Grant (50%*1065*40%) - Year 1			213
Est. net cost to WCC			2635



#### Planned "Insulate" Works '23/'24 Part 2 - delivery programmes

2023 2024 July Aug Sept Oct Nov Dec Jan Feb Mar

Voids - internal wall insulation (IWI) (closing programme for trials)

SHDF - Swedish cottages (already tendered/award pending)

SHDF - Loft insulation top-ups/ventilation (already tendered/award pending)

RR - Energy assessments (Phases 1 - 160 complete) (Phase 2 tendered/award pending)

RR - Insulation top-up and/or ventilation (subject to tenant uptake)

Cavity wall suck-outs/refills (50% already tendered/award pending)

RR- Cavity wall suck-outs/refills ( 50% already tendered/award COR- Single glazed window replacements (conservation areas)

RR - Single-glazed door replacements (will be carred out concurrently with above if not before)

Voids - houses, bungalows and top floor flats (loft insulation) (already procured)


Voids - houses & bungalows (cavity insulation) (already procured)

Planning Procurement/Award Site Delivery



### **EPC uplift after SHDF, R&R, Void Pilot, Airey Pilot:**

SAP BAND	DISTRIBUTION			
SAP:	No. of Homes	% of Homes	% Rounded	Fabric Programme: SHDF + R&R + Void Pilot + Airey Pilot
Α	33	0.654632017	1	33 / (0.65%)
В	<mark>235</mark>	4.661773458	5	238 / (4.7%)
С	<mark>3042</mark>	60.34516961	60	<mark>3412 / (68%)</mark>
D	<mark>1703</mark>	33.78297957	34	<mark>1341 / (26%)</mark>
_ E	<mark>25</mark>	0.495933347	0	<mark>16 / (0.3%)</mark>
Page	2	0.039674668	0	<mark>0</mark>
g G	1	0.019837334	0	1(0.019%)
Total stock in count	5041	100.00	100	5041
Average SAP :	70.55			371 properties move to EPC C & 3 to EPC B



#### **Procurement Challenges**

Significant amount of Wave 2 funding, but limited number of contractors

Frameworks for accredited contractors have "tied up" resource/closed to new members

Specialist PAS 2035 framework - all 8 invited - only 1 bid returned

Costs associated with this work have increased significantly (the single bid received was significantly higher than estimate)

WCC is a small authority, with relatively small packages of work to offer

Very high premiums being paid for accredited installers

WCC procurement rules frustrate and limit the speed of procurement (tender thresholds quickly exceeded)

CP dules have standing vfm requirement, but difficult to warrant in highly inflated/ premium market

ge

7


#### **Procurement Solutions**

For non-SHDF properties, not build to Trustmark standards (similar to passivhaus premium issues)

Investigate dedicated internal workforce option to service the demand (eg. trial loft insulation installations with Special Maintenance?)

Investigate joint procurement options - review and report back


Plan to incorporate retrofit works into major term contract re-procurements




## **Engagement / advice / information**

- Work to date
  - Resident survey (Dec 2022), focus group (Feb & March 2023) & ongoing information sharing with service delivery group
  - Initial branding discussion with service delivery group
  - Project plan and policy approach to strands to allow for effective tenant engagement/consultation
- Programmed work
  - Engagement & communications strategy evidence value through engagement options
  - Resident liaison post specialist officer leading on tenant engagement, providing advice & support for tenants
  - Further focus groups to give a customer focus to project strands
  - Recruit resident champions for project strands
  - Regular targeted communications newsletters, podcasts, Facebook/tweets, competitions/activities, community events
  - Home user guides/technical equipment guides, FAQs, hints & tips, website information

# Questions?





This page is intentionally left blank